





_									
		NOZZLE SCHEDULE							
	ITEM	SIZE	RATING	TYPE	MATL	PROJ IN	PROJ OUT	REMARKS	
	Α	4''	N.P.T.	W.F.	C.S.	STD.	STD.	EMERGENCY VENT OPENING	
	В	2''	N.P.T.	W.F.	C.S.	STD.	STD.		
	С	3/4"	N.P.T.	W.F.	C.S.	STD.	STD.	DRAIN	









NOTES:

- MATERIAL: H.R. CARBON STEEL
- DESIGN & OPERATING PRESSURE: ATMOSPHERIC. В.
- DESIGN & OPERATING TEMPERATURE: AMBIENT.
- TANK TO BE BUILT & LABELED PER U.L. SPEC. #142. D.
- TANK TO BEAR MANUFACTURERS & U.L. LABELS ONLY.
- TANK TO BE AIR TESTED WITH WATER & SOAP SUDS SOLUTION.
- INTERIOR: REMOVE WELD SLAG (SHIP CLEAN & DRY). G.
- EXTERIOR: GRAY PRIMER INCLUDED; SEE SALES ORDER FOR TOP COAT.
- ALL FITTINGS TO BE PROTECTED FOR SHIPMENT.
- CUSTOMER HAS THE RESPONSIBILITY TO VERIFY ALL DIMENSIONS.

APPROVAL FOR CONSTRUCTION SCHEDULE A - MASTER TERMS & CONDITION OF SALE*

APPROVED AS DRAWN.

APPROVED WITH NOTED CHANGES, CONSTRUCTION WILL BE SCHEDULED WHEN SIGNED DRAWING AND CONFIRMED ORDER ARE RECEIVED.

SIGNATURE:

SALES ORDER: -

CLARION

www.oneclarion.com

PO Box 700338 Wabasso, FL 32970 863-261-8388

All units inches

unless stated

otherwise

info@oneclarion.com

DESCRIPTION:

300 GALLON RECTANGULAR UL 142 SINGLE WALL TANK

CUSTOMER: DATE: 2/8/2023 DWG.# FTSBSW-0300 DRAWN BY: CHKD BY: